BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of the Work: Improvements to drains roads in maruthi farm, in Amruthanagara A sector in ward no.07, Byatarayanapura

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	800.30	Earthwork excavation by manual means in rodinary soil involving an average horizontal throw upto 2 m and an average lift upto 1.5m, excavated surafce levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking clods complete as per specifications.all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	137.80	Rupees One Hundred Thirty Seven and Eighty Paise Only
2	110.25	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration inlcuding curing for 14 days including cost of all materials labour, HOM curing, form works, scaffolding and centering complete as per specification all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	5421.90	Rupees Five Thousand Four Hundred Twenty One and Ninety Paise Only
3	1451.25	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.7.5 cm thick all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	742.00	Rupees Seven Hundred Forty Two Only
4	187.80	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4 with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work. all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	859.66	Rupees Eight Hundred Fifty Nine and Sixty Six Paise Only
5	1035.00	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete10cms thick.all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	966.72	Rupees Nine Hundred Sixty Six and Seventy Two Paise Only
6	1236.00	KSRB 5-8.1: Providing one line dressing to granite stone slabs/granite stone masonry as per specifications.all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	950.82	Rupees Nine Hundred Fifty and Eighty Two Paise Only
7	4045.00	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc., complete.all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Nos	467.46	Rupees Four Hundred Sixty Seven and Forty Six Paise Only
8	1820.00	KSRB 5-9.1:Providing and applying ready mix priming coat over ocncrete / masonry, / asbestos cement sheet / plastered surfaces includding preparing the surface after thorougly cleaning of oil, grease, dirt and other foreign matter and sand papering including cost of materials, labour compelte as per specifications. all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	39.22	Rupees Thirty Nine and Twenty Two Paise Only
9	370.00	Providing and fixing MS Grating 260x260 mm all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Nos	84.75	Rupees Eighty Four and Seventy Five Paise Only
10	800.30	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	94.34	Rupees Ninety Four and Thirty Four Paise Only

	Quantity.	Description	Unit	Rates	
				In Figures	In Words
11	135.00	Laying Reinforced cement concrete pipe NP3 for culverts inlcduding ends and fixing collars with cement mortar 1:2 including cost of materisla, labour, curing including cost of materials, labour HOM complete as per specifications. B. 750 mm dia all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Mtr	3676.08	Rupees Three Thousand Six Hundred Seventy Six and Eight Paise Only
12	15.20	Providing 100mm and down size nominal size. all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	987.62	Rupees Nine Hundred Eighty Seven and Sixty Two Paise Only
13	5.09	Providing 40mm and down size nominal size all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	1091.43	Rupees One Thousand Ninety One and Forty Three Paise Only
14	5.09	Providing 20mm and down size nominal size all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	1091.43	Rupees One Thousand Ninety One and Forty Three Paise Only
15	3.82	Providing Fine aggrgate 2.36mm nominal size all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Cum	1054.29	Rupees One Thousand Fifty Four and Twenty Nine Paise Only
16	90.00	Providing and fixing MS Grating 260x260 mm all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Nos	89.84	Rupees Eighty Nine and Eighty Four Paise Only
17	45.00	Direction and place identification signs upto 0.9 sqm size Board - Providing and erecting direction and place identification retro-reflectorised signs as per revised IRC : 67-2012 made of high intensity grade sheeting vide clause 800.1.3, fixed over aluminium sheeting, 2mm thick with area not exceeding 0.9 sqm supported on a mild steel single angle iron post 75x75x6mm firmly fixed to the ground by means of properly designed foundation with M-15 grade cement concrete 45x45x60cm, 60cm below ground level as per approved drawing complete as per specifications. MORTH Specification No.801 Type IV sheeting all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Nos	7274.78	Rupees Seven Thousand Two Hundred Seventy Four and Seventy Eight Paise Only
18	381.50	Providing and applying readymix priming coat concrete / masonry / asbestos cement sheet /plasterd surface including preparing the surface after throughly cleaning of oil grease dirt and other foreign matter and sand papering cost of materials labour as per specifications all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	39.22	Rupees Thirty Nine and Twenty Two Paise Only
19	4712.50	Supply MS. Pipe. 25mm dia & 25mm thick all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Mtr	84.75	Rupees Eighty Four and Seventy Five Paise Only
20	501.50	Painting on Steel surface :- Providing and applying two coats of ready mix paint of approved brand after through cleaning of surface to give an even shade complete as per specifications.complete as per specifications. MORTH Specification No.803 all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	Sqm	76.32	Rupees Seventy Six and Thirty Two Paise Only
21	78750.00	Painting new latter and figures any shade with synthetic enamel paint black or any approvel colour to give an even shede complete as per specification (I) Hindi (Matras commas and the like not to be measured and paid for half latter shall be counted as half) all leads and lift etc., complete as directed by the Engineeri-in-charge of the work.	cms	1.06	Rupees One and Six Paise Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed
2 Unit rates and prices shall be quoted by the Tender in Indian rupees.
3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)
4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the

( ) ರಲ್ಲಿ ವಿವರಿಸಿರುವಂತೆ ಅಂಕ
ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು(
ಹಿದ್ದುಮಾಡಿಗಳ ಒಟ್ಟು ಸಂಖ್ಯೆ :
ರದ್ದುಗೊಳಿಸುವ ಒಟ್ಟು ಪುಟಗಳ ಸಂಖ್ಯೆ :
ಅಧೀಕ್ಷಕ ಅಭಿಯಂತರರು ( )